



City of Portsmouth

Office of the City Manager

728 Second Street
Portsmouth, Ohio 45662



TO: Portsmouth City Council
FROM: City Manager Derek K. Allen, ICMA-CM *DKA*
DATE: September 18, 2017
RE: City Manager's Report September 25, 2017

Municipal Building

The boiler for the Municipal Building has been installed.

The collapsing sewer underneath the Municipal Building has been filled with concrete and three manholes were filled and the manhole ring and lid were removed from Spruce Alley and Vine Alley.

Parks

A purchase order has been issued for the fence replacement at the Mound Park tennis courts.

Streets

The ordinance, contract, approved invoice and check for the Westbound US 52 resurfacing project were delivered to ODOT's District 9 office in Chillicothe on September 15, 2017. The construction start date is June 30, 2018 with a completion date of September 30, 2018.

The 2017 resurfacing program is being awarded to Shelley Paving and it is anticipated that the resurfacing will be conducted in October.

The design for the widening and reconstruction of Pershing Avenue is complete and is ready for bid.

Grandview widening design is still on-going.

The fence repair in Sciotoville along US 52 has been completed.

The bids are out for salt and the bid opening is scheduled for September 29, 2017 at 1:00.

Traffic

The thermoplastic pavement markings project 2017 has been completed. The project utilized thermoplastic for school crosswalks and school markings.

Wastewater

September 5, 2017: 1044 Kent Street, repaired six inch (6") sanitary sewer tap. Cleaned basins due to rain.

September 6, 2017: 2930 Coles Ridge, repaired two (2) storm catch basins. Old Post Road, repaired storm basin.

September 7, 2017: Robison Avenue, cleaned sewer.

September 8, 2017: Charles Street and Mary Ann Street, repaired storm catch basin. Delivered vactor truck to Cincinnati for repair.

September 11, 2017: 2136 7th Street, replaced six inch (6") sanitary sewer tap. 1858 Coles Boulevard, 5530 4th Street, dye tested sewers.

September 12, 2017: Various locations, cleaned catch basins due to rain.

September 13, 2017: Municipal Building, cleaned sewers in preparation for filling with high density fill. 623 Bonser Avenue, Smoke tested.

September 14, 2017: Municipal Building. Filling abandoned sewer with flowable mortar. 934 30th Street, dye tested.

September 15, 2017: Municipal Building. Removed basins and completion of sewer abandonment.

The phosphorus study, which is mandated by Ohio EPA, will be conducted in house at a savings of \$27,500.

Water

September 6, 2017: Repaired two inch (2") main 20 Dalton Lane. Exposed six inch (6") main 8400 block of Hayport Road.

September 7, 2017: Installed three (3) taps 8400 block of Hayport Road.

September 11, 2017: Repaired thirty inch (30") main 2200 block of Sunrise Avenue. (A four foot (4') section of main).

